TECHNICAL DATA/SPECIFICATIONS *

RATED LOAD: 750 lbs maximum.

INPUT POWER SOURCE:

-AC POWERED UNIT: 110-120 Volt 8 Amp 60 Hz dedicated service.
-DC BATTERY POWERED UNIT: 110-120 Volt 3 Amp 60 Hz battery charger.

DRIVE:

-AC POWERED UNIT: 1/2 hp motor, 1750 rpm, 90 VDC, continuous duty.

-DC BATTERY POWERED UNIT: VPL-3100B: 1/2 hp motor, 1750 rpm, 24 VDC, continuous duty.

VPL-3200B: 1 hp motor, 1750 rpm, 24 VDC, continuous duty. Dual 4L style Poly-V belts and pulleys, 3.94:1 pulley reduction.

INTERMEDIATE REDUCTION: Dual 4L style Poly-V belts and pulleys, 3.94:1 pulley reduction. FINAL DRIVE: VPL-3100: 1" dia. ACME screw w/bronze nut and bronze safety back up nut.

VPL-3200B: 1.25" dia. ACME screw w/bronze nut and bronze safety back up nut.

MOTOR CONTROLLER:

-AC POWERED UNIT: 24 VAC Relay control.
-DC BATTERY POWERED UNIT: 24 VDC Relay control.

SPEED:

-AC POWERED UNIT: 9 feet per minute maximum.
-DC BATTERY POWERED UNIT: 10 feet per minute maximum


PERFORMANCE STANDARDS


USA FOOD & DRUG ADMINISTRATION: CLASS II, 510(K) Exempt, File No. 890.3930,

Product Code: PCE

ASME A18.1 (Section 5) Safety Standards for Platform Lifts and Stairway Chairlifts * CSA B355 Lifts for Persons with Physical Disabilities (Residential Application) * CSA B44.1/ASME A17.5 Elevator and Escalator Electrical Equipment *


* For complete technical specifications and performance standards years of compliance please see: ILS-00834 "VPL-3100 Series Residential Vertical Platform Lift Technical Specification" ILS-00986 "VPL-3200B Series Residential Vertical Platform Lift Technical Specification"














	D	E	F	G	Н	J	K	L
36" X 4 8 " P L A T F O R M	36-1/4"	33-1/2"	30-3/4"	5-3/4"	48-7/16"	64-5/8"	31-9/16"	50-13/16"
36" X 5 4 " P L A T F O R M	36-1/4"	33-1/2"	30-3/4"	8-3/4"	54-7/16"	70-5/8"	31-9/16"	50-13/16"
36" X 6 0 " P L A T F O R M	36-1/4"	33-1/2"	30-3/4"	11-3/4"	60-7/16"	76-5/8"	31-9/16"	50-13/16"
42" X 60" PLATFORM	42-1/4"	39-1/2"	36-3/4"	11-3/4"	60-7/16"	76-5/8"	34-9/16"	56-13/16"

	Α	В	С
VPL-3153	7 5-9/16"	95"	5 3"
VPL-3175	9 7-9/16"	117"	7 5"
V P L - 3210B	1 4 8-1/16"	165"	123"
V P L - 3212B	172-1/16"	189"	147"
VPL-3214B	196-1/16"	213"	171"







NOTES: 1) ACCESS RAMP CAN BE MOUNTED ON EITHER SIDE OF THE PLATFORM 2) SEE ILS-00938 FOR LANDING GATE DETAIL/ALIGNMENT

(OPTIONAL)

ILS-00932 **SHEET 2 OF 5** REV. 9 (6760)(10/10/18)(BG)

Bruno Independent Living Aids, Inc., 1780 Executive Drive, P.O. Box 84, Oconomowoc, WI 53066 Phone (800) 882-8183 Fax (262) 953-5501

Any reproduction or other use of these materials without written permission of Bruno Independent Living Aids, Inc. is expressly prohibited. Bruno Independent Living Aids, Inc. reserves the right to modify or make changes to these specifications at any time with out notice.



ANCHOR POINT LOCATIONS/SLAB DETAIL

TECHNICAL SPECIFICATIONS *


FLOOR ATTACHMENT:

VPL MUST BE FASTENED TO CONCRETE SLAB USING FOUR (4) 1/2" (3/8" BOLT) X MINIMUM 2-1/2" LONG CONCRETE ANCHORS SUITABLE FOR THE ENVIRONMENT. FOLLOW SELECTED CONCRETE ANCHOR MANUFACTURERS GUIDELINES AND APPLICABLE CODES.

FLOOR REQUIREMENTS:

4" THICK 3500 PSI MINIMUM COMPRESSIVE STRENGTH, REINFORCED CONCRETE SLAB.

* For complete technical specifications please see ILS-00834 "VPL-3100 Series Residential Vertical Platform Lift Technical Specification" ILS-00986 "VPL-3200B Series Residential Vertical Platform Lift Technical Specification"




UNITS WITH STRAIGHT THROUGH PLATFORM

	М	N	P	Q
36"X48" PLATFORM	7-5/8"	12-1/16"	66"	54"
36" X 5 4 " P L A T F O R M	10-5/8"	15-1/16"	72"	54"
36" X 6 0 " P L A T F O R M	13-5/8"	18-1/16"	78"	54"
42" X 60" PLATFORM	13-5/8"	18-1/16"	78"	60"

ILS-00932 **SHEET 3 OF 5** REV. 9 (6760)(10/10/18)(BG)




Bruno Independent Living Aids, Inc. reserves the right to modify or make changes to these specifications at any time with out notice.



RIGHT SWING
PLATFORM GATE
SHOWN OPEN

RIGHT & LEFT SWING
PLATFORM GATES
AVAILABLE

	Α	В	С
VPL-3153	7 5-9/16"	9 5"	5 3"
VPL-3175	9 7-9/16"	117"	7 5"
VPL-3210B	1 4 8-1/16"	165"	123"
VPL-3212B	172-1/16"	189"	147"
VPL-3214B	196-1/16"	213"	171"



GATE NOT SHOWN

14 7/8"
MIN SLAB

*MIN. FLOOR TO FLOOR
OF VPL-3175 IS 28"

NOTES: 1) ACCESS RAMP & PLATFORM GATE CAN BE MOUNTED ON EITHER SIDE OF THE PLATFORM

2) SEE ILS-00938 FOR LANDING GATE DETAIL/ALIGNMENT

ILS-00932 SHEET 4 OF 5 REV. 9 (6760)(10/10/18)(BG)

-CIRCUIT BREAKER

BOX (VPL-3100 SERIES)

G OF PLATFORM

Bruno Independent Living Aids, Inc., 1780 Executive Drive, P.O. Box 84, Oconomowoc, WI 53066 Phone (800) 882-8183 Fax (262) 953-5501

Any reproduction or other use of these materials without written permission of Bruno Independent Living Aids, Inc. is expressly prohibited. Bruno Independent Living Aids, Inc. reserves the right to modify or make changes to these specifications at any time with out notice.



ANCHOR POINT LOCATIONS/SLAB DETAIL

TECHNICAL SPECIFICATIONS *


FLOOR ATTACHMENT:

VPL MUST BE FASTENED TO CONCRETE SLAB USING FOUR (4) 1/2" (3/8" BOLT) X MINIMUM 2-1/2" LONG CONCRETE ANCHORS SUITABLE FOR THE ENVIRONMENT. FOLLOW SELECTED CONCRETE ANCHOR MANUFACTURERS GUIDELINES AND APPLICABLE CODES.

FLOOR REQUIREMENTS:

4" THICK 3500 PSI MINIMUM COMPRESSIVE STRENGTH, REINFORCED CONCRETE SLAB.

* For complete technical specifications please see ILS-00834 "VPL-3100 Series Residential Vertical Platform Lift Technical Specification" ILS-00986 "VPL-3200B Series Residential Vertical Platform Lift Technical Specification"



	N	Р	Q	R
36" X 4 8 " P L A T F O R M	7-5/8"	12-1/16"	67-1/2"	54"
36" X 5 4 " P L A T F O R M	10-5/8"	15-1/16"	73-1/2"	54"
36" X 6 0 " P L A T F O R M	13-5/8"	18-1/16"	79-1/2"	54"
42" X 60" PLATFORM	13-5/8"	18-1/16"	79-1/2"	60"

UNITS WITH STRAIGHT THROUGH PLATFORM WITH PLATFORM GATE

